Project Description:

ADNOC BAB UHTW/UHTW 4.750/4.750

Test Run Description:

- Pre-test work required on stationary and rotating seal faces.
  - Waviness measurement on 1 location
  - Taper measurement on 2 locations
  - Roughness measurement
  - Profile measurement
  - Height stationary face (only carbon and SIC30)
- Install mechanical seals per drawing listed above
  - OB: #1 and #2 / IB: #3 and #4
  - when possible install thermocouple at IB and OB seal stationary face.
- Pressurize to indicated pressure, measure break-out torque. Repeat torque measurements after 10 minutes.
- Start Test Unit
- Stop test unit and measure break-out torque. Repeat torque measurements after 10 minutes.
- Post-test work Job and plug seal, required on stationary and rotating seal faces.
  - Waviness measurement on 1 location
  - Taper measurement on 2 locations
  - Roughness measurement
  - Profile measurement
  - Height stationary face (only carbon and SIC30)

Seal Information:

Reference Drawing: F00321662 / D0527190-2 revB

	Inboard Seal	Outboard Seal
Seal Type and Size:	UHTW 4.750	UHTW 4.750
Stationary Seal Face	C100603033 (SIC30)	C100603033 (SIC30)
Rotating Seal Face:	C100603035 (SL WAVY)	C100603038 (SL WAVY)
Spring(s):	668838NL (9)	668838NL (10)

Test Conditions:

Test Unit:	B
Duration:	min 75 hours
Speed:	2980 rpm

	Process Fluid	Barrier Fluid
Test Medium:	NA	Water
Pressure:	NA	70 barg
Inlet Temperature:	NA	60°C
Flow:	NA	TBD l/min